

## **Fencing Overview and Maintenance Strategy**

### **Fencing Overview**

In accordance with the September 2<sup>nd</sup>, 2018 Approved Site Plan the Project will install a wire mesh agricultural fence that is approximately 4 feet tall around the perimeter of the project and equipment. There will be a gate at the entrance for access as needed. The fencing consists of wood posts with animal friendly wire mesh, complete with proper signage and security. This fencing will retain low visibility with the proposed plant screening and blend in naturally with the environment.

### **Fencing Maintenance**

The proposed wire mesh will be inspected bi-annually. Fence will be checked for loose parts each year to make sure the integrity of the fence is maintained. Holes and rotted wood will be replaced. Oil on the most vulnerable parts will occur on a regular basis. Replacement for damage parts will be done on an as needed basis. Vegetation along the fence will be managed periodically. The forest and shrub zones will not be touched unless necessary in order to enhance the screening as much as possible.