




20 SHEPHERDS WAY Town of Washington, NY C-101



9. Periodic inspection and needed maintenance shall be provided after each rain.

#### STABILIZED CONSTRUCTION





- SILT FENCE SPECIFICATIONS
- 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL EITHER "T" OR "U" TYPE OR HARDWOOD.
- FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
- FENCE SHALL BE WOVEN WIRE, 12 1/2 GAUGE, 6" MAXIMUM MESH OPENING. 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER FILTER X,
- MIRAFI 100X, STABILINKA T140N, OR APPROVED EQUIVALENT.
- 4. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUIVALENT. 5. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN

"BULGES" DEVELOP IN THE SILT FENCE.

SILT FENCE

# SYMBOL —— SBD —— DRAINAGE AREA NO MORE THAN 1/4 ACRE PER 100 FEET OF STRAW BALE DIKE FOR SLOPES LESS THAN 25%. ANGLE FIRST STAKE TOWARDS -PREVIOUSLY LAID BALE.

#### DIKE SPECIFICATIONS

- 1. BALES SHALL BE PLACED AT THE TOE OF A SLOPE OR ON THE CONTOUR AND IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.
- 2. EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF (4) INCHES, AND PLACED SO THE BINDINGS ARE HORIZONTAL.
- 3. BALES SHALL BE SECURELY ANCHORED IN PLACE BY EITHER TWO STAKES OR RE-BARS DRIVEN THROUGH THE BALE. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE AT AN ANGLE TO FORCE THE BALES TOGETHER. STAKES SHALL BE DRIVEN FLUSH WITH THE BALE.
- 4. INSPECTION SHALL BE FREQUENT AND REPAIR REPLACEMENT SHALL BE MADE
- 5. BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULLNESS SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

## STRAW BALE DIKE


PROJECT NUMBER 569-01

#### **EARTHWORK SPECIFICATIONS**

- 1. All graded or disturbed areas including slopes shall be protected during clearing and construction in accordance with the approved erosion and sediment control plan
- 2. All sediment control practices and measures shall be constructed, applied and maintained in accordance with the approved erosion and sediment control plan.
- 3. Topsoil required for the establishment of vegetation shall be stockpiled in amount
- necessary to complete finished grading of all exposed areas. 4. Areas to be filled shall be cleared, grubbed, and stripped of topsoil to remove
- 5. Areas which are to be topsoiled shall be scarified to a minimum depth of four inches prior to placement of topsoil.
- 6. All fills shall be compacted as required to reduce erosion, slippage, settlement, subsidence or other related problems. Fill intended to support buildings, structures and conduits, etc. Shall be compacted in accordance with local requirements or
- 7. All fill shall be placed and compacted in layers not to exceed 9 inches in
- 8. Except for approved landfills, fill material shall be free of frozen particles, brush, roots, sod, or other foreign or other objectionable materials that would interfere with or prevent construction of satisfactory fills.
- 9. Frozen materials or soft, mucky or highly compressible materials shall not be
- 10. Fill shall not be placed on saturated or frozen surfaces.


trees, vegetation, roots or other objectionable material.

- 11. All benches shall be kept free of sediment during all phases of development.
- 12. Seeps or springs encountered during construction shall be handled in accordance with the standard and specification for subsurface drain or other approved method.
- 13. All graded areas shall be permanently stabilized immediately following finished
- 14. Stockpiles, borrow areas and spoil areas shall be shown on the plans and shall be subject to the provisions of this standard and specification.



#### CONCRETE WASHOUT SPECIFICATIONS

- Location: Locate the facility a minimum of 100 feet from drainage swales, storm drain inlets, wetlands, streams and other surface waters. Prevent surface water from entering the structure except for the access road. Provide appropriate access with a gravel access road sloped down to the structure. Signs shall be
- Liner: All washout facilities will be lined to prevent leaching of liquids into the ground. The liner shall be plastic sheeting with a minimum thickness of 10 mils with no holes or tears, and anchored beyond the top of the pit with an earthen berm, sand bags, stone, or other structural appurtenance except at the access
- 4. If pre-fabricated washouts are used they must ensure the capture and containment of the concrete wash and be sized based on the expected frequency of concrete pours. They shall be sited as noted in the location
- Accumulated hardened material shall be removed when 75% of the storage capacity of the structure is filled. Any excess wash water shall be pumped into a containment vessel and properly disposed of off
- The plastic liner shall be replaced with each cleaning of the washout facility.



- evaporation of the wash water and rainfall. Wash water shall be estimated at 7 gallons per chute and 50 gallons per hopper of the concrete pump truck and/or discharging drum. The minimum size shall be 8 feet by 8 feet at the bottom and 2 feet deep. If excavated, the side slopes shall be 2 horizontal to 1 vertical.
- placed to direct drivers to the facility after their load is discharged.

- All concrete washout facilities shall be inspected daily. Damaged or leaking facilities shall be deactivated
  and repaired or replaced immediately. Excess rainwater that has accumulated over hardened concrete
  should be pumped to a stabilized area, such as a grass filter strip.
- Dispose of the hardened material off-site in a construction/demolition landfill. On-site disposal may be allowed if this has been approved and accepted as part of the projects SWPPP. In that case, the material should be recycled as specified, or buried and covered with a minimum of 2 feet of clean
- Inspect the project site frequently to ensure that no concrete discharges are taking place in non-designated areas.





REVISIONS Description Date 12/19/22 1 fencing added 2 entrance adjustments 1/19/23 3 coordination 6/14/23

November 21, 2022




75 PALATINE PARK RD. GERMANTOWN, NY (845) 758-5434

SCHOOL BUILDING FOR EVANGELICAL FREE CHURCH, INC. BOVEE CONSTRUCTION

20 SHEPHERDS WAY TOWN OF WASHINGTON, NY

SEDIMENT AND **EROSION CONTROL** C-103



#### SCHEDULE OF INVERTS

Lowest Sewerable Invert: Building sewer @ <sup>1</sup>/<sub>4</sub>"/ft, 12' +/- [0.25'] effluent line @  $\frac{1}{8}$ "/ft, 4' +/- shown [0.04'] 301.2' Pump Chamber inlet: solid pipe 50'@  $\frac{1}{8}$ "/ft [0.52'] Lateral #8: 302.0'

Standard Notes for Commercial Projects (Onsite Water Source & Sewage Disposal) - w/PWS

The design, construction and installation shall be in accordance with this plan and generally accepted standards in effect at the time of construction which include:

"New York State Design Standards for Intermediate Sized Wastewater Treatment Systems", NYSDEC "Appendix 75-A, Waste Treatment - Individual Household Systems, New York State Sanitary Code." "Recommended Standards for Sewage Treatment Works, (Ten States)."

"Recommended Standards for Water Works (Ten States)." "New York State Department of Health and Dutchess County Environmental Health Services Division policies, procedures and standards." "Dutchess County and New York State Sanitary Codes."

"Dutchess County Environmental Health Services Division Certificate of Approval letter."

This plan is approved as meeting the appropriate and applied technical standards, guidelines, policies and procedures for arrangement of sewage disposal and treatment and water supply facilities.

Upon completion of the facilities, the finished works shall be inspected, tested, and certified complete to the DCDH by the New York State registered design professional supervising construction. No part of the facilities shall be placed into service until accepted by the DC EHSD.

Approval of any plan(s) or amendment thereto shall be valid for a period of 5 years from the date of approval. Following the expiration of said approval, the plan(s) shall be re-submitted to the Commissioner of Health for consideration for re-approval. Re-submission or revised submission of plans and/or associated documents shall be subject to compliance with the technical standards, guidelines, policies and procedures in effect at the time of the re-submission.

All wells and onsite wastewater treatment system existing or approved within 300 feet of the proposed wells and onsite wastewater treatment system are shown on this plan along with any other environmental hazards in the area that may affect the design and functional ability of the onsite wastewater treatment system and well.

It shall be demonstrated by the contractor to the DC EHSD field inspector and/or design professional that the tank is sealed, watertight and acceptable for use. This shall require, at a minimum, the filling of the tank with water to observe if it is in fact sealed, watertight and acceptable for use. The tank must also meet any local testing requirements, including possible electrical and safety standards.

All proposed wells and service lines on this plan are accessible for installation and placement.

No cellar, footing, floor, garage, cooler or roof drains shall be discharged into the onsite wastewater treatment

All buildings shall be constructed at an elevation high enough to ensure gravity flow to the onsite wastewater treatment system.

There shall be no vehicular traffic over the onsite wastewater treatment system. Prior to construction, the area of the system shall be staked out and fenced off.

Onsite wastewater treatment systems shall not be installed in wet or frozen soil.

The DC EHSD shall be notified prior to the backfilling of any completed onsite wastewater treatment system so that a final inspection may be performed.

The DC EHSD shall be notified sixty days prior to any change in use; use changes may require re-approval by the DC EHSD.

All required Erosion & Sediment Control and Stormwater Pollution Prevention Water Quality & Quantity Control structures, permanent and temporary, are shown on the plans.

#### Additional Notes for Fill Sections

Septic Fill Specification: Sand and gravel fill, with a stabilized percolation rate which is less than or equivalent to the percolation rate of the virgin soil, and no more than 15 minutes per inch shall be used.

A New York State registered design professional shall certify in writing that the fill material is in the proper location, of the proper quantity and dimensions, and of proper quality. Proper quality must be demonstrated by stabilized percolation tests, the results of which shall be submitted with the engineer's certification.

Prior to the placement of the fill, the area of the OWTS shall be cleared of debris, and all brush, trees, or other vegetation cut to the level of the virgin ground. No topsoil shall be removed unless specifically indicated on the

The undersigned owners of the property hereon state that they are familiar with this map, its contents and its

legends and hereby consent to all said terms and conditions as stated hereon.

Existing well to be abandoned in accordance with requirements of AWWA-100 standard. Excavate at existing casing to a depth of at least 5 ft., cut off casing and fill with grout or bentonite or both to overflowing, then backfill to grade. 2500g H20 pump chamber 8-Outlet (min.) distribution box w/ locking MH covers, inlet invert 301.5 min. Proposed additional well for high school building Existing School, Parish Hall and Sanctuary FF Elev. 299.50 Existing concrete Existing pump Existing leaching bed disposal – Existing well to be modified by extending area with concrete galleys casing above grade, see well dètail

SOIL TEST RESULTS PERCOLATION TESTS Presoaked on 11/22/2022 and tested on 11/23/2022 by T. Lynch according to the standard procedure. PT-3 24" Silty Loam DEEP TESTS: By Timothy A. Lynch, P.E. and Ron Miller, PE/S.P.H.E. November 15, 2022 DT-6 (@ existing) Total depth 7.0 ft. No rock or water -no DCDBC rep. 6"-8" topsoil; Total depth 7.0 ft. mottling at 5.5 ft. Loamy, fine gravel 6"-24"; Water at 6.5 ft. Very silty loam 24"-66"; Till at 66"-70" Balance course gravel.

> Loamy, fine gravel 6"-18"; Very silty loam 18"-36"; Gravel 36"-54" Till at 54"-60" Balance course gravel. Total depth 8.0 ft. No rock or water 6" +/- topsoil; mottling at 6.5 ft. Loamy, fine gravel 6"-30"; Fine Gravel 30"-78" Till at 78"+ Total depth 8.8 ft. No rock or water 6" +/- topsoil; mottling at 6.7 ft. Loamy, fine gravel 6"-20":

Total depth 7.5 ft.

No rock or water 6" +/- topsoil; mottling at 4.5 ft.

Fine Gravel 20"-80" Till at 80"+ Total depth 7.3 ft. No rock Water at 7.3 ft. 6" +/- topsoil; mottling at 6.7 ft. Loamy, fine gravel 6"-20"; Fine Gravel 20"-80" Till at 80"+

### O.W.T.S. DESIGN DATA

Design Basis: High School w/ no food service; 83 Students maximum at 12 gpd/st, design flow is 996 gpd. PRIMARY DISPOSAL AREA - Design Percolation Rate is 6


Per table 4b, the application rate is 1.0 gpd/sf and the minimum length of trench is therefore 996/1.0/2= 498 l.f.; 498 x 75% (for gravelless type system) = 374' Install eight (8) lines of twelve units (=8 x 12 x 4 ft. = 384 l.f.) for

1.5 FEET (minimum) OF FILL REQUIRED - see indicated grading - 12" -18" of Gravel; 6" of Topsoil

RESERVE AREA - Design same as above.


The OWTS has been designed to handle wastewater flow from a maximum three (3) bedroom dwelling and any increase in the number of bedrooms shall require submission of plans prepared by a NYSPE to DCDH for review and approval of additional sewage disposal and treatment facilities.





NOTE: Refer to detail sheet C-501 and related sheets: C-101 Existing Conditions C-102 Site Plan C-103 Erosion and Sediment Control Plan

DC DBCH



BOVEE CONSTRUCTION

Tax Parcel IDs: T. Washington: 135889-6566-00-648951; T. Clinton: 6566-02-587843; T. Stanford: 6567-00-703007


SCHOOL BUILDING FOR EVANGELICAL FREE CHURCH, INC. 20 SHEPHERDS WAY TOWN OF WASHINGTON, NY


WATER SUPPLY AND WASTEWATER DISPOSAL PLAN & NOTES C-104





REVISIONS No. Description Date March 15, 2023 PROJECT NUMBER 569-01


75 PALATINE PARK RD. GERMANTOWN, NY (845) 758-5434























BOVEE CONSTRUCTION

SCHOOL BUILDING FOR
EVANGELICAL FREE CHURCH, INC.
20 SHEPHERDS WAY
TOWN OF WASHINGTON, NY

WATER SUPPLY AND
WASTEWATER DISPOSAL
DETAILS

C-501